

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23150-00-00
Spot: NESWNWNW Sec/Twnshp/Rge: 3-9S-23W
815 feet from N Section Line, 550 feet from W Section Line
Lease Name: QUINT Well #: 3-1
County: GRAHAM Total Vertical Depth: 3850 feet

Operator License No.: 6861
Op Name: RON'S OIL OPERATIONS INC
Address: 1889 200 AVENUE
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3849	0	150 SX CMT.
SURF	8.625	259	0	150 SX CMT.

\$ 125.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2006 9:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: RON NICKLESON Company: RON'S OIL OPERATIONS, INC. Phone: (785) 421-2409

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2006 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

ELI perforated two holes at 1930' and 1025'.
Allied pumped 25 sxs 60/40 pozmix - 10% gel neat, followed with 130 sxs cement with 400# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
Pumped 45 sxs down backside with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3788	3790		
3774	3778		
3752	3756		
3630	3632		
3570	3574		

INVOICED

DATE: 1-9-07

INV. NO. 2007061102

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams

(TECHNICIAN)

RECEIVED

Form CP-2/3

DEC 29 2006

KCC WICHITA

DEC 18 2006

RON'S OIL OPERATIONS
PENOKEE KS 67659

3-09S-23W
815' FNL & 550' FWL, SEC

#3-1 QUINT

site: 4 S & 1-1/4 W OF HILL CITY KS
contr: ANDERSON DRILLING #1

cy: GRAHAM
field: BRUSH CREEK EXT (1/2 E)

API 15-065-23150

gd: _____
fr date 03/03/2006 spd date 03/09/2006 drg comp 03/15/2006 card issued 09/04/2006 last revised 09/04/2006

ELV: 2246 KB, 2241 GL LOG
tops.....depth/datum
ANH.....1902 +344
B/ANH.....1937 +309
TOP.....3335 -1089
HEEB.....3551 -1305
TOR.....3574 -1328
LANS.....3591 -1345
BKC.....3801 -1555
RTD.....3850 -1604

IP status:
TEMP ABD, 08/01/2006
CSG: 8-5/8" 217 / 150 SX (ALT 2), 4-1/2" 3850 / 150 SX
COMMENT: MI & RURT 3/9/2006
NO CORES
DSTS TAKEN - DETAILS NA
TRGT ZN: LKC (OIL), PTD 4000 (LKC), MICT (6/23/2006) -
CO, PF (LKC) 3788-3790, W / 4 SPF, AC 250 GAL (MA), SWB
LD, RE-AC 750 GAL (15%), SWB LD, SO, PF (LKC) 3774-3778,
W / 4 SPF, AC 250 GAL (MA), SWB LD, RE-AC 750 GAL
(15%), SWB LD, SO, PF (LKC) 3752-3756, W / 4 SPF, AC 250
GAL (MA), SWB LD, RE-AC 750 GAL (15%), SWB LD, SO, PF
(LKC) 3630-3632, W / 4 SPF, AC 250 GAL (MA), SWB LD,
RE-AC 750 GAL (15%), SWB LD, SO, PF (SNYDVLE)

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)