

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-01256-00-00
Spot: SWNESW Sec/Twnshp/Rge: 26-12S-22W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: OGALLAH UNIT Well #: 4-5
County: TREGO Total Vertical Depth: 4036 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4019	0	w/unknown sxs cement
SURF	8.625	304	0	w/unknown sxs cement

131.17

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/11/2006 12:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2006 3:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 3575' - pumped 100 sxs 60/40 pozmix - 10% gel cement with 400# hulls.
Pulled 2500' - circulated with 140 sxs cement.
Topped off with 25 sxs cement.
Tied onto backside - pumped 100 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
4019	4036		
3997	4012		

INVOICED
DATE 1-9-07
INV. NO. 2007061105

Remarks: LEASE ORIGINALLY KNOWN AS SCHOENTHALER #5. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Case Morris

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

DEC 26 2006 Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

DEC 21 2006

PKT

PYRAMID DRILLING

#5

SCHOENTHALER

26-12-22W
SW NE SW

Contr.

TREGO

County

E 2352 RR Comm.

Comp.

8-1-52

IP

349 BOPD

PHY POT

Tops	Depth	Datum
LANS	3608	-1256
B/KC	3849	-1497
CONG	3951	-1599
ARB	4014	-1662
TD	4032	-1680

Casing

8" 300

5" 4014

ACID 500; EST 16

BOPD; DD 4032; INC

OGALLAH

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS