

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 137-00644-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 4-16-58.

Well Operator: R.P. Nixon Operations, Inc. KCC License #: 5252  
(Owner / Company Name) (Operator's)  
Address: 207 West 12th Street City: Hays  
State: KS Zip Code: 67601 Contact Phone: ( 785 ) 628 - 3834  
Lease: Wiltout Well #: 6 Sec. 27 Twp. 5 S. R. 21 ☐ East ☒ West  
C - NE - NE - NE Spot Location / QQQQ County: Norton

330 Feet (in exact footage) From ☒ North / ☐ South (from nearest outside section corner) Line of Section (Not Lease Line)  
330 Feet (in exact footage) From ☒ East / ☐ West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: ☐ Oil Well ☐ Gas Well ☐ D&A ☐ Cathodic ☐ Water Supply Well  
☒ SWD Docket # D-6484 ☐ ENHR Docket # \_\_\_\_\_ ☐ Other: \_\_\_\_\_

Conductor Casing Size: none Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8 5/8" Set at: 223' Cemented with: 160 Sacks  
Production Casing Size: 5 1/2" Set at: 3642' Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: well originally dry and plugged on 5-6-58. Attempted to complete well - open hole Reagan Sand from 3642'-3661'. L/KC perforations: 3572'-75', 3470'-72', 3438'-3440'. Current perms (Cedar Hills) from 1365'-1538'. PBDT: 1840'

Elevation: 2223 (☐ G.L. / ☒ K.B.) T.D.: 3661' PBDT: 1840' Anhydrite Depth: 1848' (top?) taken from old driller's log  
(Stone Corral Formation)

Condition of Well: ☒ Good ☐ Poor ☐ Casing Leak ☐ Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): tie on to casing and pump cement into Cedar Hills perforations; amount of cement to be determined by KCC District #4 in Hays

Is Well Log attached to this application as required? ☒ Yes ☐ No Is ACO-1 filed? ☐ Yes ☒ No

If not explain why? too old - 1958

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Duane Achterberg  
Phone: ( 785 ) 656 - 0038 (cell)  
Address: 207 West 12th Street City / State: Hays, KS  
Plugging Contractor: R.P. Nixon Operations, Inc. KCC License #: 5252  
(Company Name) (Contractor's)  
Address: 207 West 12th Street Hays, KS 67601 Phone: ( 785 ) 628 - 3834

Proposed Date and Hour of Plugging (if known?): when location dries up from snow & ice storm

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1.4.07 Authorized Operator / Agent: [Signature]  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202


RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 08 2007  
CONSERVATION DIVISION  
WICHITA, KS

JOCELYN-VARN OIL CO #6 WILTROUT 27-5-21W  
 Contr. TRUSCO DRLG CO NE NE NE  
 E 2223 Comm. 4-16-58 Comp. 5-16-58 IP D & A  
 NORTON County

Tops	Depth	Datum
HEEB	3363	-1110
TOR	3390	-1167
LANS	3406	-1183
ARB	3641	-1418
REAG	3660	-1437
TD	3661	-1438

Casing  
 8" 223  
 5" 3642  
 DST 3320-77/1 HR, 2376' FLD (480' M,  
 890' W) BHP 1200#  
 DST 3468-88/1 HR, 240' H OCM, 30' MDY  
 SW, BHP 1232#  
 CO 3644: DD 3648: TST 5 GO & 5 GWPH:  
 ACID 1500: DD 3661: TST 1 BWPH, SCM O,  
 PERF 3572-3575: 12/3470-72: PERF 3438-40  
 PLUG 3455: TST SSO & M: ACID 1000: TST  
 31 B SWPH

RAY WEST POOL



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 JAN 08 2007  
 CONSERVATION DIVISION  
 WICHITA, KS

# KANSAS

## CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Nixon, R P Operations, Inc  
207 W 12th  
Hays, KS 67601-3810

January 08, 2007

Re: WILTROUT #6  
API 15-137-00644-00-01  
NENENE 27-5S-21W, 4950 FSL 330 FEL  
NORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



Barry Metz  
Deputy Director

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550