

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Younger Energy Company  
Address: 453 S. Webb Road, Suite 100, Wichita, KS 67207  
Phone: (316) 681-2542 Operator License #: 30705  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-145-20,697-00-00  
Lease Name: Cossman  
Well Number: 2  
Spot Location (QQQQ): \_\_\_\_\_ - SE - SW - SE  
330 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 27 Twp. 21 S. R. 15  East  West  
County: Pawnee  
Date Well Completed: 7-13-80  
Plugging Commenced: 12-13-06  
Plugging Completed: 12-14-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	926	
				4 1/2	<del>3894</del> <sup>OK</sup> <del>3730</del> <sup>PAT</sup>	2000
					<sup>3804 is OK</sup>	
					<sup>PAT KCC</sup>	
					<sup>1-12-07</sup>	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
Sanded off bottom, loaded hole with water, dug cellar, set floor, pulled slips, had 18" stretch, sand at 3595', bailed 4 sacks cement, ripped casing at 2230', worked pipe, ripped casing at 2000', came free, pulled casing up to 960', pumped 15 gel, 50 sacks, pulled to 480', pumped 50 sacks, pulled to 40', pumped 20 sacks to surface, emptied pit, cleaned up location.


Name of Plugging Contractor: Quality Well Service License #: 31925  
Address: 401 W Main, Lyons, KS 67554  
Name of Party Responsible for Plugging Fees: Younger Energy Company  
State of Kansas County, Sedgwick, ss.

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
JAN 08 2007  
CONSERVATION DIVISION  
WICHITA, KS

DIANE REBSTOCK (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Diane Rebstock, V.P. Finance  
(Address) 453 S. Webb, Suite 100, Wichita, KS 67207

SUBSCRIBED and SWORN TO before me this 2nd day of January 2007  
Stacey Williamson My Commission Expires: \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202