

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc
Address: 250 N Water, Suite 300
Phone: (316) 267-3241 Operator License #: 30606
Type of Well: P & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: December 4, 2006 (Date)
by: Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-20118-00-00
Lease Name: Irvin B
Well Number: 4
Spot Location (QQQQ): _____ - W2 - E2 - SE
1320 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 6 Twp. 14 S. R. 19 East West
County: Ellis
Date Well Completed: 10/1967
Plugging Commenced: 12/04/2006
Plugging Completed: 12/04/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	207	8.625		
		0	3865	5.50		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Quality Oilwell Cementing. Hooked-up to 8-5/8" csg. Press. to 500psi., held. Well had been squeezed. Hooked-up to tbg. Mixed 200sx 60/40 POZ 10% gel and 400# hull @ 2501'.
Pulled 48 jts. tbg. Mixed 60sx 60/40 POZ w/ 10% gel and 100# hulls @ 1017'. Pulled remaining 33 jts. tbg. Swedged into 5.5 csg. Mixed 50sx 60/40 POZ w/10% gel.
SI csg w/350 psi.

Name of Plugging Contractor: Murfin Drilling Company, Inc License #: 30606
Address: 250 N Water, Suite 300 Wichita, KS 67202


RECEIVED
KANSAS CORPORATION COMMISSION
JAN 09 2007
CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Murfin Drilling Company
State of Kansas County, Sedgwick, ss.

Susan Sears (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Susan Sears
(Address) 250 N Water, Suite 300 Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 5 day of January 20 07
E. Heibel My Commission Expires _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT