

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Cross Oil, LLC  
Address: PO Box 94  
Phone: (620) 836-5803 Operator License #: 32044  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 11-7-06 (Date)  
by: Clayton Tittle (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 1672 Bottom: 1677 T.D. 1688  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: ~~15-207-01973-00~~ 15-207-01973-00  
Lease Name: Wolfe  
Well Number: 1  
Spot Location (QQQQ): NE 1/4 - ne ne - KCC  
330 Feet from  North /  South Section Line per CPI  
330 Feet from  East /  West Section Line 1-1206  
Sec. 4 Twp. 24 S. R. 14  East  West  
County: Woodson  
Date Well Completed: 1970's unknown  
Plugging Commenced: 11-8-06  
Plugging Completed: 11-17-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	Oil	0	1688	4 1/2		749'
		0	unknown	10'		none, surface casing

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing and packer was hung up in hole, so ran 1" to 1625' and pumped 25 sacks of cement. Pulled 1" out of hole and shot the 2" tubing off @ 941' and pulled. Unscrewed and pulled 749' of 4 1/2" casing and ran 2" tubing to a depth of 705'. Pumped 40 sacks of cement @ 705' and pulled tubing to 269' and pumped cement to surface. Pulled rest of tubing out of hole and topped off cement in hole.

Name of Plugging Contractor: Consolidated Oil Well Service License #: 31440  
Address: PO Box 103  
Name of Party Responsible for Plugging Fees: Cross Oil, LLC  
State of Kansas County, Greenwood, ss.

Dennis R. Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Dennis R. Smith  
(Address) \_\_\_\_\_

SUBSCRIBED and SWORN TO before me this 24 day of November, 20 06  
Sandra L. Smith My Commission Expires: 3-16-2010  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**SANDRA L. SMITH**  
Notary Public, State of Kansas  
My Appt. Expires 3-16-2010

*PRT*