

4-060995

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

11-2

API Number: 15-163-21,025 00-00
SE SE NW /4 SEC. 26, 08 S, 17 W
2970 feet from S section line
2970 feet from E section line

Operator license# 5134

Lease Hrabe Well # 6-26

Operator: Graham-Michaelis Corporation

County: Rooks 112.61

Address: 211 North Broadway
Wichita, Kansas 67202

Well total depth 3465 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 259 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: Box 209 - Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 2 Month: November Year: 1996

Plugging proposal received from: Mike Kelso/Manny

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 210 sxs 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines 12-2-96

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:30 P.M., Day: 2, Month: November, Year: 1996

Actual plugging report: 8 5/8" to 259' w/150 sxs. 4 1/2" to 3463' w/150 sxs. Perfs at 3177' - 3182' - 3240' - 3244' and 3301' - 3305'. Sanded to 3125' w/4 sxs cement with dump bailer. Shot casing at 1719' and 1354' with no free pipe. Mixed and pumped 60 sxs cement with 200# hulls and displaced to 850'. Shot casing at 850'. Mixed and pumped 30 sxs cement with 150# hulls and displaced to 400' Shot casing at 400' and 280'. Pipe free at 280'. Circulated cement with 70 sxs cement with 150# hulls. Pulled casing and topped with 15 sxs cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 1992 GL

I did / did not X observe the plugging.

[Signature]
(agent)
Form CP-2/3

INVOICED
DATE DEC 03 1996
INV. NO. 47075