

12-7

4-060477

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,237-0001

NW NW SE /4 SEC. 26, 08 S, 17 W
2310 feet from S section line
2310 feet from E section line

Operator license# 5134

Lease Ochampaugh "B" OWWO well # 1-26

Operator: Graham-Michaelis Corporation

County Rooks

Address: P.O. Box 247
Wichita, Kansas 67601

Well total depth 3473 feet ^{112.87}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 201 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 11:00A.M Day: 7 Month: December Year: 93

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 200 sxs. 60/40 posmix - 10% gel and 400# gel - 300# hulls.
Plug through casing. Annulus full to surface with "black magic" -
oil and gel mixture.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:30P.M., Day: 7, Month: December, Year: 93

Actual plugging report: 8 5/8" to 201'. 4 1/2" to 3468' w/150 sxs.
Sanded to 3080' and spotted 4 sxs. cement with dump bailer. Shot at
1725'. Didn't pull free. Pumped 35 sxs. cement with 100# hulls and
displaced to 1600'. Shot at 1500' and didn't pull free. Hung bailer
in casing at 950+. Mixed and pumped 4 sxs. gel followed by 25 sxs.
cement and displaced to 900+. Shot casing at 913'. Pulled to 825'.
Mixed and pumped 45 sxs. cement with 100# hulls. Pulled to 400' and
mixed and pumped 20 sxs. cement. Pulled casing and topped with 20 sxs.
cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES NO X
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1966 GL

I did not observe the plugging.

INVOICED
DATE 12-15-93
INV. NO. 39536

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1993
CONSERVATION DIVISION
Wichita, Kansas
(agent)
Form CP-2/3 12-14-93