

15-163-00936-00-01

4-060480

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 9-21-79

NE NE SW /4 SEC. 26 , 08 S, 17 W  
2310 feet from S section line  
2970 feet from E section line

Operator license# 5134 Lease Hrabe "D" OWWO well #1-26

Operator: Graham-Michaelis Corporation County Rooks

Address: P.O. Box 247 Well total depth 3475 feet <sup>112.94</sup>  
Wichita, Kansas 67201 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 166 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 7:30A.M. Day: 13 Month: November Year: 93

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-7943

Were: Order 200 sxs. 60/40 posmix - 10% gel.  
Plug while pulling casing.  
"Black Magic" - oil and gel in annulus.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[     ], Part[     ], None[ X ]

Completed: Hour: 12:00P.M., Day: 10, Month: December, Year: 93

Actual plugging report: 8 5/8" to 166'. 4 1/2" to 3474' w/150 sxs.  
Sand to 3100' and spot 4 sxs. cement with dumper bailer. Shot at 1725'  
and 1310'. Didn't pull free. Mixed and pumped 75 sxs. cement with 100#  
hulls and displaced to 825'. Shot at 825' and didn't pull free. Pumped  
35 sxs. cement and displaced to 450'. Shot at 450' and pulled free.  
Pumped 20 sxs. cement. Pulled casing and topped with 10 sxs. cement.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X , CALC     , NO     Dakota plug: YES X , NO      
Plugged through TUBING     , CASING X . Elevation: 1987 GL    

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 21 1993  
CONSERVATION DIVISION  
Wichita, Kansas

I did [ X ] did not [     ] observe the plugging.

INVOICED  
DATE 12-29-93  
INV. NO. 395.85  
12-10

[Signature]  
DA (agent) 12-21-93  
Form CP-2/3