

4-032039

12-29

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-21024-00-00

NW SE NE /4 SEC. 26, 08 S, 17 W  
3630 feet from S section line  
990 feet from E section line

Operator license# 5134 Lease Hrabe well # C-2

Operator: Graham/Michaelis Corporation County Rooks

Address: P.O. Box 247 Well total depth 3500 feet <sup>113.75</sup>  
211 N. Broadway Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67201-0247 Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# -

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 29 Month: December Year: 94

Plugging proposal received from: Richard

Company: Mike's Testing & Salvage, Inc. Phone: \_\_\_\_\_

Were: Order 225 sxs. 60/40 pozmix - 10% gel - 500# hulls. RECEIVED STATE CORPORATION COMMISSION  
Allied Cement Company.  
Order sand and common cement. JAN 09 1995

CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 4:15P.M., Day: 29, Month: December, Year: 94

Actual plugging report: 8 5/8" set at 250' w/165 sxs. cwc. 4 1/2" set at 3499' w/150 sxs. Perfs. 3192' - 3309'. Sand back to 3140' w/4 sxs. common cement on sand with bailer. Shots at 1750' 1280' and free pipe at 1058'. Mixed and pumped 90 sxs. cement blend to 1750' with 500# hulls mixed in. Pulled casing to 250' circulated with 95 sxs. cement blend. Pulled casing. Topped off with 20 sxs.

RECEIVED STATE CORPORATION COMMISSION

JAN 09 1995

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD  BAD  Any plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging. Carl Goodrow

**INVOICED**

DATE 1-11-95

INV. NO. 42064

(agent)

Form CP-2/3