

2-7

4-071135

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-21,001 ⁰⁰⁻⁰¹

SW SW NE /4 SEC. 26, 08 S, 17 W
2970 feet from S section line
2310 feet from E section line

Operator license# 5134 Lease Ochampaugh "A" well # 4

Operator: Graham Michaelis Corporation County Rooks

Address: P.O. Box 247 Well total depth 3405 feet
Wichita, Kansas 67201 Conductor Pipe: 0 inch @ 0 feet
Jack L. Yinger Surface pipe 8 5/8 Inch @ 171 feet

110.66

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 7 Month: February Year: 95

Plugging proposal received from: Norman Rodie

Company: Graham Michaelis Corporation Phone: 316-264-8394

Were: 8 5/8" - 171' cwc w/130 sxs.cmt. 4 1/2" casing set at 3405'
w/150 sxs. cmt. Top stage at 1300' cwc. w/250 sxs. cmt. Elv. 1983' -
Anhy. 1300' - Perfs. 3181' - 3352'. Proposal 225 sxs. 60/40 pozmix - 10%
gel and 5 sxs. hulls. Pump in with pump truck load 4 1/2" casing top to
bottom and shut in under pressure - squeeze 4 1/2" x 8 5/8" annulus with
cement. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:30A.M., Day: 7, Month: February, Year: 95

Actual plugging report: Graham Michaelis Corporation ordered 225 sxs.
60/40 pozmix - 10% gel and 5 sxs. hulls. Pumped in with pump truck.

- 1) Pumped in 4 1/2" casing with 15 sxs. cement followed with 205 sxs.
cement w/5 sxs.hulls. Max. pressure 300# P.S.I. Shut in @ 300# P.S.I.
- 2) Squeezed 4 1/2" x 8 5/8" annulus w/5 sxs. cement. Max. pressure
300# P.S.I. Shut in @ 300# P.S.I.

FEB 17 1995

2-17-95

Remarks: Cemented by: Allied Cementing - Russell, Kansas 67665

Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO

Bottom plug(in place):YES X ,CALC ,NO Dakota plug:YES X ,NO

Plugged through TUBING , CASING X . Elevation: 1983 GL

I did X / did not observe the plugging.

Marion J. Schmidt
(agent)

Form CP-2/3

INVOICED

DATE 2-22-95

INV. NO. 42250