

6-050169

8-30-95 -00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,906
NW SW NE /4 SEC. 26-, 8 S, 17 W
3630 feet from S section line
2310 feet from E section line

Operator license# 5134 Lease Ochampaugh A well # 1

Operator: Graham-Michaelis Corp County Rooks

Address: P. O. Box 247 Well total depth 3400 feet ^{110.50}
Wichita, Kansas 67201 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 168 feet

Aband. oil well XX, Gas well , Input well , SWD , D & A

Plugging contractor: Graham-Michaelis Corp License# 5134

Address: As above

Company to plug at: Hour: AM Day: 30 Month: August Year: 1995

Plugging proposal received from: Norman Rodie

Company: Graham-Michaelis Corp. phone: 316-264-8394

Were: Order out 200 sx 60/40 poz, 10% gel, 500# hulls. Pump down 4 1/2"
casing until hole full, then squeeze.
DV'd from 1280' (Anhydrite) to surface.

Plugging Proposal Received by: Bruce D. Basye RECEIVED
Plugging operations attended by agent? All[XXX], Part[], None[] STATE CORPORATION COMMISSION

Completed: Hour: 10:00 AM, Day: 30, Month: August, Year: 1995 ⁹⁻¹⁻⁹⁵

Actual plugging report: Pumped 50 sx 60/40 poz, 10% gel with 500# hulls
followed with 135 sx 60/40 poz, 10% gel down 4 1/2" casing. 400# maximum
pressure. 0# shut in. Pumped 15 sx 60/40 poz, 10% gel down 8 5/8" X 5 1/2"
annulus. 500# shut in pressure. CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Allied Cementing on location
Condition of casing(in hole): GOOD XX BAD Anhy. plug: YES XX NO
Bottom plug(in place): YES XX, CALC XX, NO Dakota plug: YES XX, NO
Plugged through TUBING, CASING XX Elevation: 1993' GL

I did / did not observe the plugging.

Bruce D. Basye
Bruce D. Basye
(agent)

INVOICED
DATE 9-11-95
INV. NO. 43504