

4-060481

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-20,901-00-00

NE SE NE /4 SEC. 26, 08 S, 17 W  
3690 feet from S section line  
270 feet from E section line

Operator license# 5134 Lease Hrabe "C" well #1-26

Operator: Graham-Michaelis Corporation County Rooks

Address: P.O. Box 247 Well total depth 3480 feet  
Wichita, Kansas 67201 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 293 feet

113.10

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 8:00A.M. Day: 14 Month: December Year: 93

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-7943

Were: Order 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[      ], Part[ X ], None[      ]

Completed: Hour: 12:00P.M., Day: 14, Month: December, Year: 93

Actual plugging report: 8 5/8" to 293'. 4 1/2" to 3479' w/150 sxs.  
Sand to 2980' and spot 4 sxs. cement with dumper bailer. Shot casing  
at 1725' and 1310' but wouldn't pull free. Mixed and pumped 75 sxs.  
cement with 100# hulls and displaced to 950'. Shot at 909' and pulled  
free. Mixed and pumped 50 sxs. cement. Pulled casing and topped with  
35 sxs. cement.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO       
Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation: 1988 GL     

I [initials] did not [initials] observe the plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
12-21-93  
CONSERVATION DIVISION  
Wichita, Kansas

Herb Deines  
(agent)

12-21-93

**INVOICED**  
DATE 12-29-93  
INV. NO. 39586