

4-041785

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

8-5

API Number: 15-163-20,670-00-00

NE SE NW /4 SEC. 26, 08 S, 17 W
3630 feet from S section line
2970 feet from E section line

Operator license# 5134

Lease: Hrabec Well # 1-26

Operator: Graham Michaelis Corporation

County: Rooks 112.45

Address: P.O. Box 247
Wichita, Kansas 67202

Well total depth 3460 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 253 feet
w/160 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing - Allied Cementing License# -

Address: Chase, Kansas 67524 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 5 Month: August Year 1996

Plugging proposal received from: Mike Testing/David

Company: Mike's Testing Service Phone:

Were: 4 1/2" casing set at 3458' w/150 sxs cement. Perf. at 3236' - 3172'.
Salt at 2000' - Anhy. at 1300'. Squeeze at 700' with 200 sxs. Perf. casing at 225'

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 A 10:51

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour P.M., Day: 5, Month: August, Year: 1996

8-21-96

Actual plugging report: Perforated casing at 2000' and 1300'. R.U. Cementers to 8 5/8" S.P. to cement annulus - blew out S.P. near surface. (Cemented from 700' squeeze.) Decided to perf at 220' to doubly insure upper protection. R.U. Cementers to pump down casing as follows: 25 sxs cement with 200# hulls followed with 8 sxs gel, followed with 125 sxs cement with 300# hulls. Shut down. Perf casing at 220' and squeezed base of S.P. while pumping. Add 75 sxs cement down casing. Max. P.S.I. 400#. S.I.P. 300#.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

INVOICED

Dennis L. Hamel
(agent)

Form CP-2/3

DATE AUG 28 1996

INV. NO. 43666

MD