

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-19055-00-00
Spot: SESESW Sec/Twnshp/Rge: 6-19S-10W
313 feet from S Section Line, 3080 feet from E Section Line
Lease Name: KOWALSKY Well #: 4
County: RICE Total Vertical Depth: 3356 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S. YALE #609
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3353		125 SX CMT
SURF	8.625	256		180 SX CMT

 \$ 109.07

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2006 9:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/03/2006 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Pumped 70 sacks of cement through tubing at 2400'. Perforated at 1300', 900', and 300'. Ran tubing to 1300' and pumped 35 sacks of cement. Pulled tubing to 900' and pumped 35 sacks of cement. Pulled tubing to 300' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland #C031158

Perfs:

Top	Bot	Thru	Comments
3230	3241		
3198	3228		
3165	3174		
3100	3104		
3065	3074		
3041	3045		
3022	3030		

RECEIVED
KCC DISTRICT #2
OCT 30 2006
WICHITA, KS

INVOICED

DATE 1-8-07
INV. NO. 2007061064

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 29 2006

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

m

PKT