

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07445-00-00
Spot: SESWNW Sec/Twnshp/Rge: 36-19S-12W
2852 feet from S Section Line, 4433 feet from E Section Line
Lease Name: BIRZER Well #: 7
County: BARTON Total Vertical Depth: 3335 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S. YALE #609
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3332	0	150 SX CMT
SURF	8.625	169	0	150 SX CMT

\$ 108.39

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/28/2006 9:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2643

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/28/2006 4:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 575' and 1375'.
Ran tubing to 2170'.
Pumped 120 sxs 60/40 pozmix - 10% gel cement with 250# hulls.
Pulled to 1000'. Circulated with 150 sxs cement.
POOH. Tied onto backside - pumped 20 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.
Topped off casing with 20 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3235	3240		
3151	3153		
3140	3142		
3135			
3110	3116		
3083	3088		

Remarks: COPELAND CEMENTING COMPANY.

Plugged through: TBG

INVOICED
DATE 1-8-07
INV. NO. 2007061064

District: 04

Signed Case Morris
(TECHNICIAN)

DEC 20 2006

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
DEC 26 2006
CONSERVATION DIVISION
WICHITA, KS

PKT

CRESENT PETROLEUM

#7

BIRZER

36-19-12W
SW SE NW

Contr.

BARTON

County

E 1800RB Comm.

Comp. 10-21-55

IP 25 BOPD


Tops	Depth	Datum
TOP	2680	-880
HEEB	2945	-1145
TOR	2960	-1160
KC	3075	-1275
ARB	3330	-1530
TD	3335	-1535

Casing

5" 3332

CO 3335: 43 B0/10 HR

HAMMER POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS