

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22514-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 19-20S-10W
960 feet from S Section Line, 1340 feet from E Section Line
Lease Name: A R B Well #: 1
County: RICE Total Vertical Depth: 3400 feet

Operator License No.: 32924
Op Name: GILBERT-STEWART OPERATING LLC
Address: 1801 BROADWAY - SUITE 450
DENVER, CO 80202

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 307

\$ 110.50

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/13/2006 12:00 PM
Plug Co. License No.: 33724 Plug Co. Name: WARREN DRILLING, LLC
Proposal Rcvd. from: RANDY MARTIN Company: WARREN DRILLING, LLC Phone: _____

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
NOV 20 2006
WICHITA, KS

Plugging Proposal Received By: MAURICE KORPHAGE Witness Type: NONE
Date/Time Plugging Completed: 11/13/2006 4:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Filled hole with heavy mud and spotted cement through drill pipe. Spotted 50 sacks of cement at 3300'; spotted 35 sacks of cement at 1100'; spotted 35 sacks of cement at 740'; spotted 60 sacks of cement at 310', and spotted 40 sacks of cement at 60'. Pumped 10 sacks of cement in rathole and 10 sacks of cement into water well.

60/40 posmix with 6% gel

Quality Cement #115960

INVOICED
DATE 1-8-07
INV. NO. 2007061066

Remarks:

Plugged through: DP

District: 02

Signed Michael R Wilson
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

M

PKT