

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21516-00-00
Spot: SESENW Sec/Twnshp/Rge: 27-24S-9W
2020 feet from N Section Line, 2275 feet from W Section Line
Lease Name: GAGNEBIN Well #: 1-27
County: RENO Total Vertical Depth: 3865 feet

Operator License No.: 31958
Op Name: HESSE PETROLEUM CO.,L.L.C.
Address: 400 N. WOODLAWN, SUITE 7
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURE	8.625	215		

\$ 125.61

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/26/2006 7:30 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERN Company: PICKRELL DRILLING COMPANY, I Phone: (620) 793-5742

Proposed Plugging Method: Fill hole with heavy mud and spot cement through drill pipe. Spot 35 sacks of cement at 1450', 35 sacks of cement at 800'; 35 sacks of cement at 260'; 25 sacks of cement at 60'; 15 sacks of cement in rathole; and 10 sacks of cement in mousehole.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 11/26/2006 11:00 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Filled hole with heavy mud and spotted cement through drill pipe. Spotted 35 sacks of cement at 1450'; 35 sacks of cement at 800'; 35 sacks of cement at 260'; 25 sacks of cement at 60'; 15 sacks of cement in rathole; and 10 sacks of cement in mousehole.

60/40 posmix with 4% gel

Jetstar #14173

Perfs:

RECEIVED
KCC DISTRICT #2
NOV 30 2006
WICHITA, KS

Remarks:

Plugged through: DP

INVOICED
DATE 1-8-07
INV. NO. 2007061068

District: 02

Signed Michael Wilson
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

m

PKS