

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23197-00-00  
Spot: SESENE Sec/Twnshp/Rge: 9-21S-14W  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: HOLT Well #: 1  
County: STAFFORD Total Vertical Depth: 3870 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: RR 1 BOX 183B 7 SW 26TH AVENUE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3869	2360	WITH 175 SX CMT
SURF	8.625	860		WITH 450 SX CMT <u>\$125.78</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/13/2006 11:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3600' & 4 SX CMT. PLUG AT 890' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/13/2006 12:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 832'. SANDED TO 3600' & 4 SX CMT WITH DUMP BAILER. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 890' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 377' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3664	3670		SPF
3658	3660		SPF


**INVOICED**

DATE 1-8-07  
INV. NO. 2007061026

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: CSG

District: 01



Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED

DEC 23 2006

KCC WICHITA

Form

*PKT*