

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20589-00-00
Spot: ^{NW}~~W2~~SWSE ^{KCC DIST}~~1-S-857~~ Sec/Twnshp/Rge: 10-19S-2W
669 feet from S Section Line, 2431 feet from E Section Line
Lease Name: COBB C Well #: 1
County: MCPHERSON Total Vertical Depth: 3010 feet

Operator License No.: 3822
Op Name: KOEHN, ELDON R.
Address: 2241 MOCCASIN ROAD
GALVA, KS 67443

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3008		75 SX CMT
SURF	8.625	144		100 SX CMT

\$97.83

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2006 10:00 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: AARON KOEHN Company: ELDON R. KOEHN Phone: (620) 654-8656

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/05/2006 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Worked 2-1/2" tubing loose; parted at approximately 2260'. Pulled out 73 jts. Set CIBP at 2245' and capped with 2 sacks of cement. Perforated as 400'. Set bridge just below. Circulated cement to surface from 400' after loading hole with fresh water.

60/40 posmix with 4% gel

United #7390
Log Tech #4688

Perfs:

Top	Bot	Thru	Comments
2948	2970		

RECEIVED
KCC DISTRICT #2
OCT 30 2006
WICHITA, KS

INVOICED

DATE 1-8-07
INV. NO. 2007061075

Remarks:

Plugged through: CSG

District: 02

Signed *Virgil Clothier*
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 29 2006 Form CP-2/3
CONSERVATION DIVISION
WICHITA, KS

PKG