

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-02180-00-00  
Spot: SESENE Sec/Twnshp/Rge: 19-19S-9W  
2924 feet from S Section Line, 370 feet from E Section Line  
Lease Name: ROBBINS Well #: 3  
County: RICE Total Vertical Depth: 3243 feet

Operator License No.: 7200  
Op Name: LUTZ, SCOTT THOMAS, ESTATE OF  
Address: BOX 8310  
FAYETTEVILLE, AR 72703

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3242		
SURF	8.625	294		

\$ 105.40

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/19/2006 4:00 PM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: GERALD DONOVAN Company: ESTATE OF SCOTT THOMAS LUTZ Phone: (620) 786-0935

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/19/2006 7:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Ran tubing to 2930' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Perforated at 1200', 800', and 350'. Pulled tubing to 1200' and pumped 35 sacks of cement. Pulled tubing to 800' and pumped 35 sacks of cement. Pulled tubing to 350' and circulated cement to surface.

Approximately 270 sacks of cement

60/40 posmix with 4% gel

Allied #22684  
Log Tech #19817

Perfs:

Top	Bot	Thru	Comments
2979	2983		

**RECEIVED  
KCC DISTRICT #2  
OCT 27 2006  
WICHITA, KS**

**INVOICED**  
DATE 1-8-07  
INV. NO. 2007061079

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3  
DEC 29 2006  
CONSERVATION DIVISION  
WICHITA, KS

PKG