

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02183-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 19-19S-9W
4644 feet from S Section Line, 2417 feet from E Section Line
Lease Name: ROBBINS WEAVER Well #: 2
County: RICE Total Vertical Depth: 3244 feet

Operator License No.: 7200
Op Name: LUTZ, SCOTT THOMAS, ESTATE OF
Address: BOX 8310
FAYETTEVILLE, AR 72703

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3241		
SURF	8.625	130		

\$1 105.43

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2006 10:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: GERALD DONOVAN Company: LUTZ, SCOTT THOMAS, ESTATE O Phone: (620) 786-0935

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/28/2006 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Drilled out bridge at 814'. Ran tubing down to 3200' and pumped 35 sacks of cement.
Perforated at 1200', 800', and 300'. Ran tubing to 1200' and pumped 35 sacks of cement.
Pulled tubing to 800' and pumped 35 sacks of cement. Pulled tubing to 300' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #10000
Log Tech #19663

Perfs:

RECEIVED
KCC DISTRICT #2
DEC 13 2006
WICHITA, KS

INVOICED
DATE 1-8-07
INV. NO. 2007061079

Remarks:
Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3
DEC 29 2006
CONSERVATION DIVISION
WICHITA, KS

n

PKP