

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22791-00-00
Spot: SW Sec/Twnshp/Rge: 2-30S-14W
1410 feet from S Section Line, 1410 feet from W Section Line
Lease Name: ALEXANDER Well #: 1
County: BARBER Total Vertical Depth: 4685 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4570		
PROD	5.5	4680	2300	WITH 325 SX CMT
SURF	13.38	225		WITH 225 SX CMT

\$152.26

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 12/01/2006 3:15 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALAN BANGERT Company: MAI OIL Phone: (214) 219-8883

Proposed Plugging Method: PUMP 200# HULLS & 40 SX CMT. PLUG AT 800' WITH 12 SX GEL & 50 SX CMT. PLUG AT 260' WITH 100 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/05/2006 12:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 40 SX COMMON CMT. DISPLACED PLUG TO 3950'. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 800' WITH 15 SX GEL & 50 SX CMT. PULLED UP TO 250' TO SPOT 2ND PLUG. HOLE WOULD NOT LOAD. DID NOT SPOT PLUG. RUN IN WITH SLICK LINE & FOUND TOP OF PLUG AT 950'. SDON. 12/4/06: RUN 5 1/2" CASING BACK TO 800'. PUMPED 1000# OF HULLS IN WITH 50 SX GEL. NO RETURNS. PUT 80 BBLs OF DRILLING MUD DOWN HOLE. PUMPED DOWN 5 1/2" CASING WITH ANOTHER 1000# HULLS IN WITH 50 SX OF GEL. HAD NOT RETURNS. SPOT 50 SX COMMON CMT WITH 3% CC AT 800'. NO RETURNS SDON. 12/5/06: TAG TOC WITH WIRELINE AT 810'. RUN 5 1/2" CASING BACK IN TO 760'. PUT 80 BBLs OF DRILLING MUD DOWN HOLE. SPOTTED 800# HULLS AHEAD & 200# HULLS IN WITH 100 SX COMMON CMT WITH 3% CC & 1% AMMONIA AT 760'. NO RETURNS. PULLED 5 1/2" CASING OUT OF CMT. WAIT ON CMT TO SET. RUN IN WITH SLICK LINE & TAG TOP OF CMT AT 460'. LOAD HOLE & CIRCULATE. EXCELLENT RETURNS. SPOT 100 SX COMMON CMT WITH 3% CC AT 250'. LAST PLUG SPOTTED AT 40' WITH 100 SX CMT. A GOOD DEAL OF CMT WAS PUT IN WELL CELLAR. HOLE STAYED FULL.


Perfs:

Top	Bot	Thru	Comments
4203	4206		
4086	4090		
4066	4070		
4040	4046		

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT W/3% CC & 1% AMMONIA BY ALLIED.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

DEC 26 2006

CONSERVATION DIVISION
WICHITA, KS

PKT