

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24238-00-00
Spot: SESE Sec/Twnshp/Rge: 22-19S-19E
660 feet from S Section Line, 750 feet from E Section Line
Lease Name: KIPPER Well #: 22-44
County: ANDERSON Total Vertical Depth: 1224 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1201		165 SX CMT
SURF	8.625	20		4 SX CMT

39.78

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/27/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SAX COTTON SEE HULLS FROM PBDT TO 500';
CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 700' TO 4' BELOW GROUND LEVEL; CUT CASING AND
WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 04/27/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING AND TOP OFF WELL. PUMP TOTAL OF 130 SACKS OF POZ MIX. WELL PLUGGED.

RECEIVED
KCC DISTRICT #3

DEC 18 2006 FG

CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
1141	1143		
1124	1126		
1118	1121		
1112	1114		
1076	1078		
902	904		
881	883		
865	867		
837	839		
822	824		

INVOICED
DATE 1-8-07
INV. NO. 2007061082

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 22 2006

CONSERVATION DIVISION
WICHITA, KS

Remarks: OPERATER PLUGGED WELL

Plugged through: TBG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

FG