

15-073-19510-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Greenwood County. Sec. 22 Twp. 23 Rge. 10 (E) (W)

Location as "NE/CNW4SW4" or footage from lines SESW SW
Lease Owner Rodney Dimick
Lease Name Pearson Well No. 2
Office Address Hamilton, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed April 1959 19
Application for plugging filed Aug. 28, 1970 19
Application for plugging approved Sept. 1970 19
Plugging commenced Sept. 21, 1970 19
Plugging completed Sept. 25, 1970 19
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marvin Corkery
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2262 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		797'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bridged hole at 2000', rocks, mixed and dumped 3 sacks cement.
Pulled casing. Bridged hole at 200', rocks and 12 sacks
cement to 135', bridged hole at 50 ft., rocks and 8 sacks cement
to top.

RECEIVED
STATE CORPORATION COMMISSION
10/16/70
OCT 16 1970
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Lewis C. Long
Address Hamilton Kansas

STATE OF Kansas COUNTY OF Greenwood, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Long
Hamilton Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of Oct, 19 70

My commission expires 7-23-72

Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
8/31/70
AUG 31 1970
CONSERVATION DIVISION
Wichita, Kansas

Company: Throgmorton and Sauder

Farm: Pearson

Well: #2

Location: SE SW SW 22-23-10-Greenwood County

Date: April 27, 1959

Contractor: Eureka Drilling Company

Rig: #1

Figures indicate bottoms of formations:-

10	lime
106	shale and shells
200	shale w/lime strks
250	shale
565	shale w/lime strks
610	shale
970	shale and lime
1010	shale w/lime strks
1190	shale
1255	sandy shale
1295	sand
1445	lime
1575	shale w/lime strks
1610	lime
1700	lime w/shale brks
1745	lime
1840	shale and lime strks
2040	shale and shells
2090	shale
2180	sandy shale
2200	shale w/lime strks
2212	shale
2232	sand and sandy shale
2241	sand S. O.
2262	core #1 sand and shale

60 ft 7" casing
cemented to top

2234' 4 1/2" OD pipe
cemented w/ 80 sks.