

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

**Locate well correctly on above
Section Plat**

Greenwood County. Sec. 22 Twp. 23 Rge. 10 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$

Lease Owner W. H. Geise

Lease Name Tom Edwards Well No. 1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed July 5 1951

Application for plugging filed July 7 1951

Application for plugging approved 19

Plugging commenced July 7 1951

Plugging completed July 11 1951

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?..... yes.....

Name of Conservation Agent who supervised plugging of this well..... A. W. Hartsook.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 2174 Feet.....
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom hole mudded heavy
4 1/2" ripped 1600 ft. pulled and more mud in hole
150 ft. from top and cemented with seven
sacks of cement. mudded to top and cemented
with five sacks of cement and covered with soil

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Robert I. Moore
Address Yates Center, Kansas

STATE OF Kansas, COUNTY OF Woodson ss.

_____ (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature)

SUBSCRIBED AND SWORN to before me this 8th day of August, 1951.

My commission expires

23-5091-s 8-50-10M

PLUGGING

FILE SEC 24 23 R OC

BOOK PAGE 94 LINE 39

8/9/51
AUG 9 X 1951

CO. 1st INFANTRY DIVISION

15-073-19504-00-00

WELL LOG

DRILLED FOR: W. H. Giese,
ADDRESS: Virgil, Kansas.

LOCATION: SW cor. SE/4 NW/4, Sec. 22-23-
10; Greenwood County, Kansas.

CONTRACTOR: Sauder Drilling Co
ADDRESS: Gridley, Kansas.

CASING:	run	pulled	size
	810'	810'	10"
	1270'	1270'	8"
	1625'	1625'	7"
	2137'	Cmt'd 2137' W/40Sx4½"	

FARM: Edwards WELL #1

COMMENCED: March 12, 1951
COMPLETED: April 3, 1951

Shot from 2142 to 2166 W/20 Qts
Nitro-Glycerin.

TOTAL DEPTH: 2174'

PRODUCTION: Est 10 Bbls.

0 to 4' Soil	910 Shale
25 Lime	935 Lime
36 Shale	955 Shale
45 Lime	960 Lime
56 Shale	976 Shale
62 Lime	1030 Lime
75 Shale	1119 Shale
85 Lime	1155 Lime
90 Shale	1160 Shale 7-BW 1175-80
95 Lime	1215 Lime
150 Shale	1236 Sand HFW
155 Lime	1270 Lime
160 Shale	1275 Shale
165 Lime	1410 Lime
171 Shale	1506 Shale
175 Lime	1530 Lime
195 Shale	1535 Sand HFW
200 Lime-1BW	1580 Lime
215 Shale	1595 Shale
225 Lime	1685 Lime
230 Shale	1750 Shale
235 Lime	1775 Lime
250 Shale	1805 Shale
275 Lime	1810 Lime
315 Shale	1815 Shale
330 Lime	1835 Lime
360 Shale	1850 Shale
365 Lime	1860 Lime
395 Shale	1937 Shale
405 Lime	1950 Lime
460 Shale	1952 Shale
495 Lime	1965 Lime
540 Shale	1975 Shale
594 Lime	1980 Lime
605 Shale	2060 Shale
612 Lime	2065 Lime
640 Shale	2095 Shale-Dark
660 Lime	2105 Shale-Light
680 Shale	2125 Shale-Dark
695 Lime	2132 Shale-Sandy
700 Shale	2137 Broken Sand
725 Lime	2174 Sand-Bartlesville
730 Shale	2174 Total Depth.
745 Lime	
770 Shale	
780 Lime	
810 Shale	
822 Lime	
875 Shale	
900 Lime	



RECEIVED
STATE OF KANSAS
8/9/51
AUG 9 X 1951
CONSERVATION DIVISION
Wichita, Kansas