

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-02991
(Well Completed
API NUMBER November 24, 1953)
LEASE NAME Stamper "C"
WELL NUMBER #3
SPOT LOCATION SE SE NE
SEC. 32 TWP. 8S RGE. 17W (W)
COUNTY Rooks
Date Well Completed 11-24-53
Plugging Commenced 11-13-84 2:30 P.M.
Plugging Completed 11-13-84 3:30 P.M.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.
ADDRESS P.O. Box 352, Russell, KS 67665

PHONE # (913)483-3144 OPERATORS LICENSE NO. 5135

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3401' bottom 3406' T.D. 3406'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3401'	06'	8-5/8"	158'	none
				5-1/2"	3402'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mixed 50 sks. cement - 10 sks. gel - 50 sks. cement - 10 sks. gel - 150 sks. cement. Maximum pressure 700#, shut-in 300#. Mixed 100 sks. cement down backside. Maximum pressure - 500#, shut-in 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor John O. Farmer, Inc. License No. 5135
Address P.O. Box 352, Russell, KS 67665

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III (~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~)

(operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665



SUBSCRIBED AND SWORN TO before me this 16th day of November, 1984

Margaret A. Schulte
Notary Public
Margaret A. Schulte

My Commission Expires: January 27, 1985

STAMPER C #3

SE/4 SE/4 NE/4 of Section 32-8S-17W Rooks County, Kansas

Rigged up rotary tools 11/13/53
Tore down rotary tools 11/24/53

Ran 5 Jts (158') 8 5/8" Rd Thd new pipe set at 157'. Cemented with 150 sacks cement, 200# Cal. D1.
Ran 109 Jts (3427.72') 5 1/2" 8 Rd Thd pipe set at 3402(. Cemented with 100 sacks cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	
Sod & shale	0'	157'	
Shale & shells	157	840	
Dakota Sand	840	995	
Redbed & shells	995	1275	
Anhydrite	1275	1308	
Redbed & shells	1308	1455	
Redbed, shale & shells	1455	1700	
Redbed, shale & lime streaks	1700	1790	
Shale & lime	1790	2145	
Lime	2145	2431	
Shale & Lime	2431	2460	
Shale & lime streaks	2460	2540	
Lime & shale	2540	2755	
Shale & lime streaks	2755	2850	
Lime	2850	2935	
Shale & lime	2935	3050	
Lime	3050	3062	
Shale & lime	3062	3122	
Lime & shale streaks	3122	3157	
Lime	3157	3285	
Lime & shale	3285	3348	
Lime	3348	3401	
Arbuckle	3401	3406	TD

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1953

CONSERVATION DIVISION
Wichita, Kansas

I, W. M. Barnett, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

W. M. Barnett

Subscribed and sworn to before me this 27th day of November, 1953.

Jane Swaney

My commission expires: July 29, 1957

15-163-02991-00-00

OCT 30 1984

STAMPER C #3

CONSERVATION DIVISION
Wichita, Kansas

SE/4 SE/4 NE/4 of Section 32-8S-17W Rooks County, Kansas

Rigged up rotary tools 11/13/53
Tore down rotary tools 11/24/53

Ran 5 Jts (158') 8 5/8" Rd Thd new
pipe set at 157'. Cemented with 150
sacks cement, 200# Cal. Bl.
Ran 109 Jts (3427.72') 5 1/2" 8 Rd
Thd pipe set at 3402(. Cemented with
100 sacks cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sod & shale	0'	157'
Shale & shells	157	840
Dakota Sand	840	995
Redbed & shells	995	1275
Anhydrite	1275	1308
Redbed & shells	1308	1455
Redbed, shale & shells	1455	1700
Redbed, shale & lime streaks	1700	1790
Shale & lime	1790	2145
Lime	2145	2431
Shale & Lime	2431	2460
Shale & lime streaks	2460	2540
Lime & shale	2540	2755
Shale & lime streaks	2755	2850
Lime	2850	2935
Shale & lime	2935	3050
Lime	3050	3062
Shale & lime	3062	3122
Lime & shale streaks	3122	3157
Lime	3157	3285
Lime & shale	3285	3348
Lime	3348	3401
Arbuckle	3401	3406 TD

I, W. M. Barnett, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

W. M. Barnett

Subscribed and sworn to before me this 27th day of November, 1953.

James Swancy

My commission expires: July 29, 1957