


15-163-03201-00-20

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Rooks County. Sec. 32 Twp. 8S Rge. 17W (X) (W)  
Location as "NE/CNW/SW" or footage from lines NE NE SE  
Lease Owner Petroleum, Inc.  
Lease Name Brown "E" Well No. 1-B  
Office Address Route 2, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed October 8, 19 51  
Application for plugging filed April 11, 19 59  
Application for plugging approved April 15, 19 59  
Plugging commenced June 11, 19 59  
Plugging completed June 18, 19 59  
Reason for abandonment of well or producing formation Depletion of  
Producible Zones  
If a producing well is abandoned, date of last production March 31, 19 59  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas  
Producing formation Kansas City Depth to top 3100' Bottom - - - - Total Depth of Well 3340' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	194'	None
				4-1/2"	3260'	1722'
Kansas City	Water and Little Oil	3183'	3185'			
		3185'	3191'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

(Plugged back to 3223')

Made bridge plug at 3130'. Filled hole with crushed rod from 3130' to 3120'. Placed 5 sacks cement on top of rock. Pulled 35 joints of casing and pumped plug to 538'. Pumped in 30 sacks commercial gel, lost circulation before mud reached the surface. Pulled 1 joint of casing and pumped in 20 sacks commercial gel. Broke circulation and placed 20 sacks cement at 500'. Pulled 9 Joints of casing and pumped in 11 sacks commercial gel. Broke circulation and placed 20 sacks cement at 170'. Pulled remaining 4 joints of casing and filled hole to the base of well cellar with 10 sacks cement.

STATE CORPORATION COMMISSION  
JUN 25 1959  
CONSERVATION DIVISION  
Wichita, Kansas  
6/25/59

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Morgan Well Plugging Service  
Address 102 West 18th Street, Hutchinson, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle  
ROUTE 2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 59  
Arthur J. Niles  
Notary Public.

My commission expires April 11, 1963

PLUGGING  
FILE SEC. 32 T. 8 R. 17W  
BOOK PAGE 30 LINE 22

# WELL LOG

COMPANY **Petroleum, Inc.**

SEC. 32 T. 8 R. 17

FARM **TWIN BROWN 'E' B-#1** NO. **1**


LOC. **NE NE SE**

TOTAL DEPTH **3340'**

COUNTY **Rooks County, Kansas**

COMM. **September 18, 1954.** COMP. **September 28, 1954.**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 194' w/135 sax.**  
**4 1/2" @ 3260' w/80 sax.**

ELEVATION **1959 RB**

PRODUCTION **Lansing**

FIGURES INDICATE BOTTOM OF FORMATIONS

50	Surface Clay & Rock	<b>Tops:</b>
194	Sand & Shale	Heebner: 3061 (-1102)
950	Shale, Sand & Shells	Toronto: 3079 (-1120)
1266	Shale & Red Rock	Lansing: 3100 (-1141)
1308	Anhydrite	
2290	Shale & Shells	
2385	Lime & Shale	
2515	Lime	
2620	Lime & Shale	
3340	Lime	
3340	R.T.D.	

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 25 1959

CONSERVATION DIVISION  
Wichita, Kansas

6/25/69

**PLUGGING**  
FILE SEC. 32 T. 8 R. 17W  
BOOK PAGE 30 LINE 20

State of KANSAS }  
County of SEDGWICK } SS:

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the BROWN 'E' B-#1 well.

*Karl E. Becker*

Subscribed and sworn to before me this 1st day of October 19 54

My Commission Expires: 8-11-58

*W. E. Edwards*  
NOTARY PUBLIC