

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-091-22848-00-01
Spot: SWSWNW Sec/Twnshp/Rge: 35-14S-24E
3060 feet from S Section Line, 370 feet from W Section Line
Lease Name: STUART Well #: 1
County: JOHNSON Total Vertical Depth: 1260 feet

Operator License No.: 32294
Op Name: OSBORN ENERGY, L.L.C.
Address: 24850 FARLEY
BUCYRUS, KS 66013

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1085		142 SX CMT 50/50 POZ
SURF	8.625	20		5 SX CMT

\$140.95

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/01/2006 8:00 AM
Plug Co. License No.: 32294 Plug Co. Name: OSBORN ENERGY, L.L.C.
Proposal Rcvd. from: JEFF TAYLOR Company: OSBORN ENERGY, L.L.C. Phone: (913) 533-9900

Proposed Plugging Method: 10 SACKS ON BOTTOM, 10 SACKS AT 470' AND FILL CASING FROM 300' TO SURFACE.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL
Date/Time Plugging Completed: 11/01/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran the tubing to 1085' and pumped 200 pounds of gel and 10 sacks of cement. Pulled the tubing to 470' and pumped 10 sacks of cement. Pulled the tubing to 300' and circulated 20 sacks of cement from 300' to surface.

Perfs:

Top	Bot	Thru	Comments
463	466		

INVOICED
DATE 1-16-07
INV. NO. 2007061197

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 08 2007

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

PKT