

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24579-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 33-17S-24W
850 feet from S Section Line, 420 feet from W Section Line
Lease Name: GANTZ TRUST Well #: 1
County: NESS Total Vertical Depth: 4430 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		WITH 180 SX CMT

\$ 143.98

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/01/2007 5:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: DUSTY RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 80 SX CMT. 3RD PLUG AT 450' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 01/01/2007 7:45 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 80 SX CMT. 3RD PLUG AT 450' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 15 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:


INVOICED
DATE 1-16-07
INV. NO. 2007061198

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 08 2007

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed Eric MacLaren
(TECHNICIAN)

Form SP-2/3

PKT