

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24354-00-00

Spot: SWSESE

Sec/Twnshp/Rge: 7-20S-15W

330 feet from S Section Line,

990 feet from E Section Line

Lease Name: LESLIE DECKERT

Well #: 1-7

County: BARTON

Total Vertical Depth: 3886 feet

Operator License No.: 33699

Op Name: T-N-T ENGINEERING, INC.

Address: 3711 MAPLEWOOD, SUITE 201  
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3912	1930	w/150 sxs cmt
SURF	8.625	1064	0	w/425 sxs cmt <u>\$ 126.30</u>

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/19/2006 9:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 797-3410

Proposed  
Plugging  
Method:

Ordered out 250 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Cut casing off at 1930'.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/19/2006 12:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Sanded back casing to 3320' and topped with 5 sxs cement using a dump bailer.  
Cut casing off at 1930'.  
Pulled up to 1750' - mixed and pumped 120 sxs cement with 300# hulls.  
Pulled up to 1050' - spotted 40 sxs cement with 100# hulls.  
Pulled up to 260' and circulated cement with 40 sxs.  
POOH. Hole full of cement.  
Topped off 12/27/2006.

**INVOICED**  
DATE 1-16-07  
INV. NO. 200 7061201

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
JAN 08 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer  
(TECHNICIAN)

Form CP-2/3

DEC 28 2006

PKT

ALLEN DRILLING COMPANY  
GREAT BEND, KS 67530

7-20 -15W  
SW SE SE

#1-7 LESLIE DECKERT

site: 3-1/2 N & 1-1/2 W OF PAWNEE ROCK, KS      city: BARTON      API 15-009-24354

contr: ALLEN DRILLING COMPANY      field: PAWNEE ROCK

geol: JEFFREY R. ZOLLER

fr      spd      drlg      card      last  
date 12/30/88      date 01/13/89      comp 01/20/89      issued 04/26/89      revised 04/26/89


ELV: 2046 KB LOG	
tops.....	depth/datum
ANH.....	1054 +992
B/ANH.....	1083 +963
WAB.....	2709 -663
TARK.....	2827 -781
HOW.....	3026 -980
TOP.....	3102 -1056
HEEB.....	3360 -1314
TOR.....	3380 -1334
DOUG SH.....	3391 -1345
LANS.....	3459 -1413
BKC.....	3681 -1635
ARB.....	3718 -1672
PBTD.....	3886 -1840

**IP status:**  
**OIL, P 53.9 BO & 240 BWPD, ARB 3738-3774 OA,**  
LTD.....3914 -1868  
RTD.....3915 -1869  
CSG: 8-5/8" 1064 / 425 SX, 5-1/2" 3912 / 150 SX  
NO CORES  
DST (1) 3670-3750 (ARB), / 30-45-45-60, 960' GIP, REC  
50' GCM, 60' SLI OIL & GCM, 1450' SLI OIL & GCMW  
ISIP 1036# FSIP 1036# IFP 553# -931# FFP 990#  
-1036# IHP 1912# FHP 1912#  
DST (2) 3754-3762 (ARB), / 30-45-45-60, SB THRU-OUT,  
GTS / 5", TSTM, REC 175' CLEAN GSY OIL, 60' OIL &  
GCM, 60' V SLI OIL & GCMW, 1625' GCW ISIP 1025#  
FSIP 1025# IFP 235# -577# FFP 648# -919# IHP 1912#  
FHP 1912#

COPYRIGHT 1989  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)