

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-21704-00-01  
Spot: E2NWSNW Sec/Twnshp/Rge: 11-24S-21E  
3620 feet from S Section Line, 3560 feet from E Section Line  
Lease Name: STEWART-HONNEUS Well #: 53 AO  
County: BOURBON Total Vertical Depth: 716 feet

Operator License No.: 33247  
Op Name: PETROL OIL & GAS, INC.  
Address: 3161 E WARM SPRINGS ROAD, SUITE 3  
LAS VEGAS, NV 89120

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	716	0	
SURF	6.625	53	0	

**# 35.00**

Well Type: EOR UIC Docket No: E26453.2 Date/Time to Plug: 12/27/2006 10:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: HARRY MALEY Company: PETROL OIL & GAS, INC. Phone: (620) 330-0491

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 716' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/27/2006 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 650'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFCE.

Perfs:

Top	Bot	Thru	Comments
673	682		

**RECEIVED**  
KCC DISTRICT #3  
JAN 10 2007 CPT  
CHANUTE, KS

**INVOICED**  
DATE 1-17-07  
INV. NO. 20070612LS

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

**RECEIVED**  
JAN 16 2007  
KCC WICHITA

Form CP-2/3

PKT