

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15576-00-00
Spot: NWNENE Sec/Twnshp/Rge: 23-20S-12W
330 feet from N Section Line, 990 feet from E Section Line
Lease Name: KOCH Well #: 1
County: BARTON Total Vertical Depth: 3337 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD, SUITE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3333	0	w/100 sxs cmt
SURF	8.625	260	0	w/unknown sxs cmt

108.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/04/2007 4:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RICK POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 653-2737

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
3080' hard mud. Holes in casing at 1500' - 2100' - 637'.
Squeezed at 264' - 289'.
Emergency plug with rig over the hole.

Plugging Proposal Received By: HERB DEINES Witness Type: PARTIAL
Date/Time Plugging Completed: 01/05/2007 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

01/04/2007 - Not witnessed by KCC Agent
RIH with tubing to 3050' - pumped 25 sxs neat.
Pulled to 1500' - pumped 120 sxs 60/40 pozmix and 3 sxs hulls to circulate cement into pit area.
Pulled tubing - pumped 30 sxs.
Max. P.S.I. 500#. S.I.P. 500#.
01/05/2007 - Witnessed by Pat Staab
Dug out backside - pumped 5 sxs 60/40 pozmix with 200# Max. P.S.I.
Blew small hole in top of head.
Topped off 5 1/2" casing with 10 sxs - standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3332	3337	OH	
3114	3274		

INVOICED
DATE 1-17-07
INV. NO. 2007061218

Remarks: QUALILTY WELL SERVICE-TICKET #1190.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

HO

JAN 08 2007

RECEIVED
JAN 10 2007
KCC WICHITA

Form CP-2/3

PST

COOP REFINERY ASS'N

#1

KOCH

23-20-12W
NW NE NE

Contr.

BARTON

County

E 1801

Comm.

Comp.

3-9-51

IP

463 BOPD

PHY POT

Tops	Depth	Datum
TOP	2716	-915
HEEB	2962	-1161
TOR	2977	-1176
BR LM	3085	-1284
LANS	3109	-1308
ARB	3332	-1531
T.D.	3337	-1536

Casing

8" 260 SWB 10 BOPH
 5" 3333 ACID 500
 SWB 15 BOPH

BRYANT POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS