

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-20763-00-00  
Spot: N2NWNW Sec/Twnshp/Rge: 27-16S-25W  
330 feet from N Section Line, 660 feet from W Section Line  
Lease Name: CONKRIGHT C Well #: 1  
County: NESS Total Vertical Depth: 4510 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH STREET  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4500	0	WITH 75 SX CMT
SURF	8.625	303		WITH 200 SX CMT

\$146.58

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/15/2006 11:30 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: GARY RICHARDS Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: SAND TO 4350' & 25 SX CMT. PLUG AT 2000' WITH 20 SX CMT. PERFORATE AT 1150'. PUMP 100 SX CMT PLUS CASING. 200 SX CMT DOWN 8 5/8".

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/15/2006 5:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 20 SX CMT WITH 100# HULLS TO 4400' THROUGH TUBING. PULLED TUBING TO 2000' & PUMPED 20 SX CMT. PULLED TUBING & PERFORATED AT 1150'. PUMPED 200 SX CMT. ON VACUUM. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 500# & HELD. TOPPED OFF CASING WITH 160 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4426	4430		
4408	4411		

INVOICED  
DATE 1-16-07  
INV. NO. 2007061198

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 08 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
DEC 27 2006  
KCC Dodge City

Signed Michael Maier  
(TECHNICIAN)

Form CC 2/3  
*[Handwritten signature]*