

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-111-20346-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 34-21S-10E  
1665 feet from S Section Line, 4494 feet from E Section Line  
Lease Name: PIXLEE C Well #: 31  
County: LYON Total Vertical Depth: 2260 feet

Operator License No.: 5697  
Op Name: JACKSON BROS., L.L.C.  
Address: 116 EAST THIRD ST.  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2226	841	
SURF	8.625	124		

*\$73.45*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/12/2006 8:00 AM  
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' cement plug @ 2130' 50' cement plug @ 841' 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/13/2006 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

built rock bridge @ 2130' mixed & dumped 5 sxs. Cement,shot casing @ 841' pumped 35 sxs cement, pulled casing to 250' pumped 90 sxs cement to surface.pulled casing out.

Perfs:

Top	Bot	Thru	Comments
2184	2211		

RECEIVED  
KCC DISTRICT #3

JAN 8 2007 *mt*

CHANUTE, KS

INVOICED

DATE 1-19-07

INV. NO. 2007061227

Remarks:

Plugged through: CSG

District: 03

Signed *Mido Heffern*  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION form CP-2/3

JAN 11 2007

CONSERVATION DIVISION  
WICHITA, KS

*PH*