

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-21098-00-00
Spot: NENESE Sec/Twnshp/Rge: 11-25S-8E
2450 feet from S Section Line, 330 feet from E Section Line
Lease Name: OLSEN B Well #: 9
County: GREENWOOD Total Vertical Depth: 2339 feet

Operator License No.: 5697
Op Name: JACKSON BROS., L.L.C.
Address: 116 EAST THIRD ST.
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2344	820	65 SACKS CEMENT
SURF	8.625	111		60 SACKS COMMON CEMENT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2006 8:00 AM
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE
Proposal Rcvd. from: _____ Company: _____ Phone: \$ 76.00

Proposed Plugging Method: 50' cement plug @ 2285' 50/ cement plug @ 820' 265' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2006 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing & washed down to 2285', pumped 25 sxs cement, pulled tubing out , shot casing @ 820' , pumped 30 sxs cement, pulled casing to 265' pumped 145 sxs cement to surface, pulled casing out, gel spacers between cement plugs.

Perfs:

RECEIVED
KCC DISTRICT #3

JAN 8 2007 MH

CHANUTE, KS

INVOICED

DATE 1-19-07
INV. NO. 2007061227

Remarks:

Plugged through:

District: 03

Signed

Mike Heffern

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JAN 11 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]