

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-23436-00-00
Spot: NENENE Sec/Twnshp/Rge: 4-22S-10E
4944 feet from S Section Line, 487 feet from E Section Line
Lease Name: PIXLEE C Well #: 33
County: GREENWOOD Total Vertical Depth: 2226 feet

Operator License No.: 5697
Op Name: JACKSON BROS., L.L.C.
Address: 116 EAST THIRD ST.
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2258	838	
SURF	8.625	204		

\$ 72.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2006 8:00 AM
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ 2226', 50' cement plug @ 883' 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2006 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

mixed & dumped 2 sxs cement @ 2226', came upto 2155' built rock bridge , mixed & dumped 6 sxs cement.shot casing @ 838', pulled casing to 800', pumped 35 sxs cement , pulled casing to 252' pumped 90 sxs cement to surface. Pulled casing out.

Perfs:

RECEIVED
KCC DISTRICT #3
JAN 8 2007 MH
CHANUTE, KS

INVOICED
DATE 1-19-07
INV. NO. 2007061227

Remarks:

Plugged through:

District: 03

Signed Mike Heffern
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 11 2007 CP-2/3
CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]