

4 060124

10-23

133 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

100' E of API NUMBER 15-163-23.118-00-00  
NE SW SE, SEC. 32, T 8 S, R 17 W/E

990 feet from S section line  
1550 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Lease Name Lewis Well # 4

Operator: Mid-Continent Energy Corp.

County Rooks 114.40

Name & Address 155 N. Market Suite 200

Well Total Depth 3520 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, KS

Company to plug at: Hour: 2:30PM Day: 23 Month: October Year: 19 90

Plugging proposal received from Matt Finnessy

(company name) Murfin Drilling Co. (phone) \_\_\_\_\_

were: Order 215 sxs. 60/40 pos 6% gel 1/4# floccel per sx.

Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXX

Operations Completed: Hour: 2:30PM Day: 23 Month: October Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3375' with 25 sxs. Arbuckle 3385'

2nd plug at 1340' with 25 sxs. Anhydrite 1322-1359'

3rd plug at 830' with 100 sxs. Dakota 528-828'

4th plug at 320' with 40 sxs. Surface pipe to 269'

5th plug at 40' with 10 sxs.

10/25/90  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied Cementing (If additional description is necessary, use BACK of this form.)

INVOICED

XXXXXX did not observe this plugging.

DATE 11-6-90

INV. NO. 29833

10-23

Herb S.

Signed [Signature] (TECHNICIAN)

Herb Deines