

6 040725

API NUMBER 15-15-163-D-16,005-28335-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW4, SEC. 32, T. 8 S, R 17 W/2

1650 - feet from S section line

2310 - feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7218

Lease Name Stamps A Well # 2-32 SWD

Operator Name: Pen. Trading and Prod. Co.

County Rooks 119.57

Address 101 N. Robinson

Well Total Depth 3679' feet

St. 840

Conductor Pipe: Size - feet -

Oklahoma, OK 73102

Surface Casing: Size 8 5/8 feet 265' w/175' ex

Abandoned Oil Well - Gas Well - Input Well - SWD Well X D&A -

Other well as hereinafter indicated -

Plugging Contractor Halliburton Contg. License Number -

Address Hays, KS

Company to plug at: Hour: 8:30 AM Day: 6 Month: 2 Year: 19 87

Plugging proposal received from Dan Cox

(company name) A.T.P. P.L.O. (phone) -

were: 5 1/2" cas set @ 3449' w/ 75' ex

D.V. @ 1266' w/ 225' ex. circ. - casing poor cond.

Packer stuck in hole - cleaned out thg & fish to @ 2759'

Ordered 250 ex 6 3/35 poz, 10% gel, 2% lite & 1/4 # flo-ale

Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part - None -

Operations Completed: Hour: 12:30 p Day: 6 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT

Ran thg. to 2750' -> pumped 50 ex 6 3/35 poz, 10% gel,
2% lite w/ 1/4 # flo-ale - pulled thg to 1420' -> pumped 60 ex
6 3/35 poz, 10% gel, 2% lite w/ 1/4 # flo-ale, circ cut to surf:
Pulled thg. -> pumped additional 40 ex cut in cas. ->
cut circ outside of S.P. area. - shut in same.

Remarks: MAX P.S.I 200 # Shut in 0 # STATE CORPORATION COMMISSION
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-11-87

INV. NO. 14122

Signed Dennis J. Hamel
(TECHNICIAN)

FEB 19 1987

CONSERVATION DIVISION
Wichita, Kansas