

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-17
API NUMBER 15-162-02992-00-00
2-54

SE NE NE, SEC. 32, T 8, S, R 17 W/E

_____ feet from S section line

_____ feet from E section line

Lease Name Stamper C Well # 5

County Rooks 110.63

Well Total Depth 3404 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 164' w/100

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Operator: John O. Farmer

Name & Address Box 352

Russell, Ks. 67665

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 4:15PM Day: 17 Month: May Year: 19 88

Plugging proposal received from Lawrence Slim Eichman

(company name) John O. Farmer (phone) _____

were: 5 1/2" casing set at 3399' w/75 sks cement. Perfs at 3119' to 3180'.

Sq at 821 w/200 sks. 2717 - 46' w/250 sks. Ordered 250 sks 65/35 Poz

10% Gel w/1/4# F.C. plus 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1988 10/21/88
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations Completed by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15pm Day: 17 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 165 sks cement w/1/4# F.C. plus

5 sks Hulls mixed in cement. Max Psi 800#. Shut in 400#. Pumped in

8 5/8" casing 35 sks cement w/1/4 F.C. Max Psi 400#. Shut in 200#.

Remarks: _____
(if additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE 10-25-88

INV. NO. 22677

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel