

15-163-03201-00-00

KANSAS  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

JUN 29 1959

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 30-22 County: \_\_\_\_\_ Rooks

Location: NE NE SE Sec. 32 Twp. 8 Rge. 17 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3340

I have this date completed supervision of plugging of:

Lease Name: Brown Well No. E-1-B

Operator's Full Name: Petroleum Inc

Complete Address: R# 2 Great Bend, Kans

Plugging Contractor: Morgan Well Service & Globe Cementing Co

Address: Hutchinson, Kans License No. 43

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 10AM Day 19 Month 6 Year 59

The above well was plugged as follows:

8 5/8" at 194' circulated with cement - 4 1/2" 3260' with 80 sax cement

PB to 3223' 1/2 perforated 3135

Filled with sand to 3120', set 3 sax cement with dump bailer, pulled

1700' 4 1/2" to 500', circulated hole with heavy mud ( 61 sax Gel)

displaced 20 sax cement through 4 1/2" at 500', heavy mud to 170',

displaced 20 sax cement through 4 1/2" at 170', heavy mud to 35', set

bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed:   
Conservation Division Agent

Reviewed:   
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 32 T. 8 R. 17  
BOOK PAGE 30 LINE 22

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 7 1959  
CONSERVATION DIVISION  
Wichita, Kansas

8/7/59