

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 148-38

LOCATION NE NE SE

SEC. 4 TWP. 9 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease J. W. Yohe

Operator Skelly Oil Co Address Hutchinson, Kans

Field _____ County Rooks

Total Depth 3466 Feet.

(Describe briefly the manner in which the well was plugged)
8 5/8" at 1357' circulated with 500 sax cement - 5 1/2" at
3466' with 200 sax cement behind- P.B. and D.M. tool set at
3106', perforations at 2400' 2300' and 2200',
Pulled 2500' 5 1/2", ~~filled~~, circulated hole full mud through tubing,
set plug at 300' with 15 sax cement run through tubing, mud to
25', set plug and filled hole to bottom cellar with cement.
Mudding and cementing by Halliburton Co.

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1952
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 4-24-52

PLUGGING
FILE SEC 4 TWP. 9 RGE. 18
BOOK PAGE 148 LINE 38