

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,658 -00-00 (of this well)

RECEIVED
STATE CORPORATION COMMISSION
2/2/77
FEB 02 1977

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Liberty Enterprises, Inc.

Complete Address Box 904, Hays, Kansas 67601

Lease Name Love-Yohe Well No. 2

Location SW SE SE Sec. 4 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3469'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Helberg Drlg.

Address Morland, Kansas License No.

Operation Completed: Hour 7:30 P Day 31 Month 1 Year 1977

The above well was plugged as follows:

RTD 3469' 8 5/8 csg set 209" cwc 150 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messing
Well Plugging Supervisor

DATE 2-2-77

INV. NO. 4578-W