

2

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,905 - 00 - 00 (of this well)

Operator's Full Name Graham- Michaelis Corp.

Complete Address P. O. Box 247, Wichita, Ks.

Lease Name Hrabe Well No. 4-26

Location SE NW NW Sec. 26 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3460'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Abercrombie Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 5:45 Day 15 Month 4 Year 1979

The above well was plugged as follows:

RTD 3460' 8 5/8 csg set 258' cwc Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1979

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

4-17-79

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 4-18-79
INV. NO. 9452.0