

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 163 - 20,855-00-00 (of this well)

10-10-78

Operator's Full Name Graham-Michaelis Corp

Complete Address Box 247, Wichita, Ks.

Lease Name Hrabe "B" Well No. 1-26

Location NW NE NE Sec. 26 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Revlin Drlg.

Address Russell, Kansas License No.

Operation Completed: Hour 8:15 A Day 9 Month 10 Year 1978

The above well was plugged as follows:

- RTD 3500' 8 5/8 csg set 322' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.
- Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.
- Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
- bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 10-12-78
INV. NO. 8279-W