

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20237-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1969
CONSERVATION DIVISION
Wichita, Kansas

8-8-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name A. Scott Ritchie

Complete Address 412 Union Center Bldg., Wichita, Kansas

Lease Name Hrabe "A" Well No. 1

Location NW NW SE Sec. 26 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3473

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drlg.

Address Wichita, Kansas License No. 598

Operation Completed: Hour 9:30A Day 5 Month 8 Year 1969

The above well was plugged as follows:

RTD 3473' 8 5/8 csg set at 201' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/8/69

INV. NO. 260-W

Signed: [Signature]
Well Plugging Supervisor