

15-163-20344-0000

Form CP-3
Rev. 6-4-68

KANSAS

SP STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1971
CONSERVATION DIVISION
Wichita, Kansas
1/18/71

Operator's Full Name Black Petroleum Inc.

Complete Address 445 O. W. Garvey Bldg., Wichita, Kansas

Lease Name Stamper "B" Well No. 1

Location SE NW SW Sec. 32 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3430'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Shields Drlg.

Address Russell, Kansas License No.

Operation Completed: Hour 10 P Day 13 Month 1 Year 1970

The above well was plugged as follows:

RTD 3430' 8 5/8 csg set at 236' cwg Gmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 225' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Ben L. Muesing*
Well Plugging Supervisor

DATE 1/18/71
INV. NO. 3231-u