

15-663-02993-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

1/21/65
RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Fender Pipe & Supply
Complete Address: Box 302 Russell, Kans
Lease Name Browne Well No. E-2
Location SW NE SE Sec. 32 Twp. 8 Rge. (E) (W) 17
County Rooks Total Depth 3414
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kans License No. 436
Operation Completed: Hour 5:30PM Day 18 Month 1 Year 65

The Above well was plugged as follows:

8 5/8" 196' circulated with cement - 5 1/2" 3409' with 50 sax cement
Sand back to 3400', set 4 sax cement with dump bailer - pulled 5 1/2"
to 550', circulated hole with heavy gel mud at 550' (10 sax Gel),
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180',
displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as hersin stated.

INVOICED

Signed: Edson Peery
Well Plugging Supervisor

DATE 1/21/65
INV. NO. 561-W