

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23338-00-00

*Per Dist 4
KCC 1-22-07*

Spot: ~~SWNWSWSE~~ SENESESW Sec/Twnshp/Rge: 12-13S-18W

929 ~~930~~ feet from S Section Line, ~~2600~~ feet from E Section Line

Lease Name: MARION STAAB Well #: 2

County: ELLIS

Total Vertical Depth: 3716 feet

Operator License No.: 6931

Op Name: BOWMAN OIL COMPANY, A GENERAL

Address: 805 CODELL RD.
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3698	0	500 SX
SURF	8.625	266	0	165 SX

\$ 120.77

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/11/2007 10:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: DON BOWMAN

Company: BOWMAN OIL COMPANY

Phone: (785) 434-2286

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 10% gel and 600# hulls.
Squeezed casing. Tubing to 2000'.
Dug out wellhead - confirmed cement in braden head.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/11/2007 2:30 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2000' - pumped 150 sxs cement with 300# hulls - no circulation - on vacuum.
Let everything set for 30 minutes - pumped 50 sxs cement - got good circulation.
Pulled tubing to 1400' - pumped 80 sxs cement with 300# hulls - good circulation.
Pulled tubing out - tied onto top and squeezed with 15 sxs cement.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3664	3668		
3616	3618		
3604	3606		

INVOICED

DATE 1-17-07
INV. NO. 2007061210

Remarks: ALLIED CEMENTING COMPANY-TICKET #32979.

Plugged through: TBG

District: 04

Signed *Marvin Mills*

(TECHNICIAN)

RECEIVED

JAN 16 2007


KCC WICHITA

Form CP-2/3

JAN 12 2007

PM

ERNST & STEINLE OIL OPERATIONS
 BOX 859 #2 MARION STAAB 12-13-18W
 RUSSELL, KS 67665 930'FSL&
 2600'FEL, SE/4
 CONTR RED TIGER DRILLING CO. CTY ELLIS
 GEOL DAVE SHUMAKER FIELD UBERT SOUTH
 ELV 2161 KB SPD 1/21/83 CARD ISSUED 6/30/83 IP P 8 BO & 60 BWPD
 2156 GL ARB OH 3693-3716 OA
 API 15-051-23,338



LOG	Tops	Depth/Datum
SC	1400 + 761	
B/ SC	1440 + 721	
TOP	3141 - 980	
HEEB	3399 - 1238	
TOR	3423 - 1262	
LANS	3448 - 1287	
BKC	3672 - 1511	
ARB	3691 - 1530	
RTD	3693 - 1532	
DDTD	3716 - 1555	

8 5/8 " 266/165SX; 5 1/2 " 3698/500SX
 NO DSTS
 MICT - CO TO 3705 TD, (ARB OH), DD 3716 TD, AC 500G, SWB
 LD, GSO, PIP, P 8 BO & 60 BWPD (GR 33.1"), 3/5/83

NOTE: 6/23/83 - ORIGINALLY FIRST REPORTED IN
 930'FSL&1300'FEL, SE/4

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS