

6090079

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,323-00-00

NE 1/4, SEC. 10, T. 9 S, R. 18 (W) W

2310 feet from N1/8 section line

2310 feet from N1/2 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

Lease Name Hageman Well # 1

Operator: Liberty Operations & Completion County Rooks

Name & Address 308 W. Mill Well Total Depth 3580 116.35 feet

Plainville, Ka 67663 Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 258'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pioneer Drilling Company License Number 5665

Address 308 West Mill Plainville, Ka. 67663

Company to plug at: Hour: Day: 3 Month: April Year: 19 84

Plugging proposal received from Tom Alm

(company name) Pioneer Drilling Company (phone) 913-434-4686

were: Order 180 sks. 50/50 permit, 4% gel, 3% Cal. Cl. + 8 5/8" wiper plug, spot all plugs w/ drill pipe w/ heavy mud between all plugs.

RECEIVED

STATE CORPORATION COMMISSION

APR 23 1984

4-23-84

Plugging Proposal Received by Edwin A. Schumacher (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:00 AM Day: 4 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug 3530' w/ 20 sks. cont.

2nd plug 1405' w/ 20 sks. cont.

3rd plug 750' w/ 80 sks. cont. + 1 sk. Alb-Flake

4th plug 300' w/ 40 sks. cont.

5th plug 40' solid bridge 1 sk. hulls 10 sks. cont.

10 sks. cont. in rat hole

Remarks: Elevation - 2026' Anhydrit - 1404' Arbuckle - yes (Allied)
(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 4-23-84

Signed Edwin A. Schumacher (TECHNICIAN)

INV. NO. 1229